



लातूर शहर महानगरपालिका, लातूर

(राष्ट्रीय शुद्ध हवा कार्यक्रम विभाग)

फोन: -02382-242803, 246075 फॅक्स: -02382-246074 ई मेल: -mclatur@yahoo.com

जा.क्र./लामनपा/रा.शु.ह.का.विभाग/ 4267/२०२३

दि. १३/०७/२०२३

ई- कोटेशन क्र. ०८-१/२०२३

प्रति,

विषय: लातूर शहर महानगरपालिके तर्फे राष्ट्रीय शुद्ध हवा कार्यक्रम (NCAP) अंतर्गत लातूर शहरातील गंजगोलाई भागात (DIGITAL DISPLAY BORD) उभा करणे करिता ई- कोटेशन देणे बाबत.

उपरोक्त विषयी आपणास कळविण्यात येते की, या कार्यालयाचे राष्ट्रीय शुद्ध हवा कार्यक्रम अंतर्गत खालील नमुद केलेल्या तपशिलाप्रमाणे लातूर शहर महानगरपालिके तर्फे राष्ट्रीय शुद्ध हवा कार्यक्रम अंतर्गत DIGITAL DISPLAY BORD उभा करणे आहे. त्याकरिता आपणा कडून बंद लिफाफ्यातून दि. २५/०७/२०२३ रोजी दुपारी ०२.०० वा. पर्यंत मा. आयुक्त, मनपा, लातूर यांच्याकडे पोहचतील असे ई-कोटेशन मागविण्यात येत आहेत. कोटेशन दि. २६/०७/२०२३ रोजी दुपारी ०४.०० वा. फोडण्यात येवून मान्य असलेल्या ई-कोटेशन भरणा-या ठेकेदारांना संबंधित काम करण्याचे कार्यादेश देण्यात येईल. आदेश दिल्यानंतर मुदतीत काम करावे लागेल. त्याकरिता खालील प्रमाणे नियम व आटी राहतील.

नियम व आटी-

- मुदती नंतर प्राप्त झालेले अथवा आटी असलेले ई- कोटेशन स्विकारले जाणार नाहीत. सुरक्षा अनामत रक्कम रु. १७०००/- नगदीने या कार्यालयात जमा केलेली पावती जोडावी लागेल. सदरील रक्कम कामाच्या दोषदायीत्व निवारण कालावधी संपल्यानंतर सहा महिन्याने सक्षम अधिका-यांनी प्रमाणित केल्या नंतर परत केली जाईल.

२. कंत्राटदारचे देयक मा. उपायुक्त तथा नोडल अधिकारी राष्ट्रीय शुद्ध हवा कार्यक्रम यांनी प्रमाणित केल्यानंतरच अदा केले जाईल. तसेच जसा निधी प्राप्त होईल त्याप्रमाणे बिल अदा केले जाईल. तथापि कांही कारणास्तव बिल अदा करण्यास विलंब झाल्यास कोणतेही प्रकारचे व्याज दिले जाणार नाही.

३. संबंधीत कोटेशनधारकांचे/ठेकेदाराचे दर मंजूर झाल्यास शासनाचे नियमा नुसार स्टॅम्प पेपरवर करारनामा करून द्यावा लागेल.

४. कामाचे कार्यदेश मिळाल्यापासुन सदरचे काम ३० (तिस) दिवसात पुर्ण करणे बंधनकारक व अवश्यक राहील.

५. करारनामा मान्य झाल्यानंतर कामाचा कार्यारंभ आदेश देण्यात येईल. त्यानंतरच काम हाती घेण्यात यावेत. कामाची सुरुवात करणे पुर्वीचे फोटो, काम करतानाचे फोटो व काम पूर्ण झाले नंतरचे फोटो सादर करणे बंधनकारक आहे.

६. निविदा धारकाच्या कसल्याही अटी व शर्ती ग्राहय धरल्या जाणार नाहीत.

७. सदरील काम हे मनपाने ठरवून दिलेल्या अटी व शर्ती प्रमाणे केले पाहिजे काम मुदतीत करावे लागेल. मुदतीत काम न झाल्यास प्रति दिवशी रु. १०००/- प्रमाणे दंड आकारला जाईल.

८. शासनाचे वेळोवेळी ठरवले अनुसार सदरील देयकातून लागू असणारे (आयकर, जीएसटी इ.) सर्व कर कपात केले जातील.

९. सदरील मिळालेले काम संबंधीत ठेकेदाराने अर्धवट सोडून दिल्यास किंवा नाही केल्यास त्यांनी भरलेली अनामत रक्कम जप्त करण्यात येईल.

१०. कोटेशन कार्यालयात सादर करावे लागेल, सिलबंद लिफाफ्यावर विभागाचा व कामाचा संदर्भ लिहावा.

११. तांत्रिक लिफाफा उघडल्या नंतर ठेकेदारांनी सादर केलेले कागदपत्राची छाननी करुन कोटेशन वैध असल्याची खात्री झाल्यानंतर अर्थीक लिफाफा उघडण्यात येईल.

१२. या व्यवहारा संबंधी कांही कारणास्तव अथवा वरील अटी व शर्ती भंग केल्यास नियमा नुसार कार्यवाही करण्याची वेळ आल्यास अथवा भाग पडल्यास किंवा हे प्रकरण न्यायप्रविष्ट झाल्यास त्याची क्षेजमर्यादा लातूर शहरा पर्यंत मर्यादीत राहील. याप्रकरणी होणारा सर्व खर्च अनामत रक्कमेतुन केला जाईल.

13. कोणतेही अथवा सर्व कोटेशन कोणतेही कारण न दाखवता नाकारण्याचे किंवा रद्द करण्याचे सर्व अधिकार मा. आयुक्त, लातूर शहर महानगरपालिका, लातूर यांनी राखून ठेवले आहेत.

14. सदरील कामावरील कर्मचा-यांचा अपघात झाल्यास किंवा कांही इजा झाल्यास त्यासंबंधी सर्वस्वी जबाबदारी कंजाटदार यांची राहिल.

15. कोटेशन फि रक्कम रु. 3400/- या कार्यालयात जमा करुन पावती सादर केल्यास ई-कोटेशन व शेड्युल 'बी' देण्यात येईल.

ई- कोटेशन सादर करावयाची पध्दत व कागदपत्र खालील प्रमाणे -

- A. Technical व Financial Documents बंद लिफाफ्यात सादर करावेत.
- B. कामाची रुपये 17000/- अनामत रक्कम व कोटेशन फि रक्कम रु. 3400/- नगदीने या कार्यालयात जमा केलेली पावती.
- C. पॅनकार्ड, आधार कार्ड.
- D. जी.एस.टी. प्रमाणपत्र, दुकान नोंदणी प्रमाणपत्र, उद्योग आधार वरील अटी व शर्ती प्रमाणे इतर सर्व/संबंधित कागदपत्रे कामाचा तपशील सोबत जोडलेला आहे.

amayum

उपायुक्त तथा नोडल अधिकारी

RawBox

राष्ट्रीय शुध्द हवा कार्यक्रम

लातूर शहर महानगरपालिका, लातूर



लातूर शहर महानगरपालिका, लातूर

(राष्ट्रीय शुद्ध हवा कार्यक्रम विभाग)

फोन: -02382-242803, 246075 फॅक्स: -02382-246074 ई मेल: -mclatur@yahoo.com

जा.क्र./लामनपा/रा.शु.ह.का.विभाग/ 4263/2023

दि. 13.09.2023

ई-कोरिशन 08/23 Scope Of Work [Gola]

Sr. No.	Product	Pitch	Description	Qty
1.	Outdoor LED Video Wall Unillimon brand company modules	P6	12.6 ft. (W) X 6.3 ft. (H) Total 79.38 SQ.FT	01
2.	A4HUIDUHDController	-	HD Controller for Execute the screen (Desktop mirror)	01
3.	Cloud Software & Training	-	HD Player Technical training	01
	AQI Software API			01
4.	Installation & Assembly	-	Installation for LED Video Wall	01
5.	Freight	-	Transportation	01
6.	Fabrication		MS Fabrication structure + Canopy structure with installation	01
8.	Voltage Stabilizer			01

Sr. No.	Parameter	Value	Unit
Led Display Screen Parameters			
1.	Pixel pitch	6	mm
2.	LED Make	King Light OR Si-milar	-
3.	Minimum viewing distance	4	Meter
4.	Brightness	>6000	Cd/m2
5.	IC Driver	MB15124 /ICN2038	-
6.	Ingress protection(Front/Rear)	IP65	-
7.	Operating temperature	-40 ~+60	Degree
8.	Operating humidity	10%-90%	-
9.	Pixel configuration	3in1,1R1G1B	RGB
10.	Pixel per s q.m.	10000	dot
11.	Grey scale	32768	Level
12.	Brightness control	256	Level
13.	Refresh frequency	>600	Hz
14.	Driving mode	Dynamic1/10ScanConstantCurrent Driving	-
15.	Blind Spot Rate	<1/10000	-
16.	Lifetimeat50%brightness	1,00,000	Hours
Led Parameters			
No.	Color	Wavelength	Unit
17.	LED Make	King Light	-
18.	Red wavelength(Typical)	623	Nm
19.	Green wavelength(Typical)	525	Nm
20.	Blue wavelengths(Typical)	470	Nm
21.	Viewing angle-H	120(+60/-60)	Deg.
22.	Viewing angle-V	120(+30/-30)	Deg.

Module Parameters			
23.	Pixel Pitch	6	Mm
24.	Pixel Configuration	1R1G1BSMDTECHNOLOGY	All Color
25.	Pixel matrix per module	80 x40	dot
26.	Module size	320 X160	Mm
Cabinet Parameters			
27.	Cabinet material	Metal Sheet with Seven tank process Powder Coating	-
28.	Cabinet Size	960 x960	Mm
29.	Cabinet Weight	35	Kg
Power Consumption			
30.	Input voltage(AC)	110 ~240	V
31.	Input power frequency	50 or60	Hz
32.	Power Consumption per Sq. Maximum	600	W
33.	Power Consumption per Sq.m Maximum	230	W
Controlling & Operating System			
34.	Signal input format	AV,S-video, VGA, DVI, Ypb PR, HDMI, SDI	-
35.	Operating system	Windows10s,10.8/8.1,7,Vista,XP,2000, NT,ME,98,95,3.x,2.0,1.0,MACOS	-
36.	Data Transfer Method	RJ45,USB,android, Cloud Base, HDMI	-
37.	Control Distance	CAT5cable<100m,Singlefibre<10km	-

OUTPUT	De Voltage	5V
	Rated Current	60A
	Current Range	0-60A
	Rated Power	300W
	Ripple & Noice(Max.)	150mVp-p
	Voltage Adj. Range	4.5-5.5V
	Voltage Tolerance	+3%
	Line Regulation	+0.5%
	Load Regulation	+2.0%
	Setup, Rise Time	1300ms,50ms/230vacATFULLLOAD
	Hold Up Time	16ms/230VACAT FULLLOAD
INPUT	Voltage Range	180-264VAC
	Frequency Range	47-63Hz
	Efficiency	83.5%
	AC Current	3.4A/230VAC
	Inrush Current	60A/230VAC
	Leakage Current	<2mA/240VAC
PROTECTION	OVERLOAD	110-140%ratedoutputpower 3.3-36vHiccupmode, recovers automatically after fault condition is removed. 48V Shut down and latch off o/p voltage, re-power on to recover.
		5.75-6.75V
	OVERVOLTAGE	3.3 36vHiccupmode,recoversautomaticallyafterfaultcondition is removed. 48V Shut down and latch off o/p voltage, re-power on to recover.
PROTECTION	OVERTEMPERATURE	3.3- 36vHiccupmode,recoversautomaticallyafterfaultcondition is removed. 48VShutdownandlatchoffo/p voltage, re-power on To recover.

FUNCTION	Fan On/Off Control	RTH3>50DEGREEFANON,<40DEGREEFANOF F
ENVIRONMENT	Working Temp.	-25TO70DEGREEREFERETODeratingcurve
	Working Humidity	20-90% RH non condensing
	Storage Temp., Humidity	-40 -+85 DEGREE,10-95%RH
	Temp .Coefficient	0.03%
	Vibration	10-500Hz

1. Scope of Supply

2. Welcome Kit from Contractor side to LCMC (Two Module, One SMPS, 5 wires, 5 Flat Cable, 20 Screws, one Screw Driver)
3. Sending card, controller, software and installation of LED is from companywide.
4. Contractor Supplier will be ensuring support LCMC throughout our customer relationship to ensure the best experience.
5. Contractor / Supplier to bear the spare cost for 1 year after installation.
6. Product transport charge to be paid by the Contractor / Supplier .
7. Contractor / Supplier strongly recommend use of Stabilizers/UPS for best user experience and life of the product.
8. Fabrication cost and completeness of project is on the Contractor / Supplier .
9. Electrification cost is on the Contractor / Supplier .
10. Contractor / Supplier to bear annual maintenance charges for 1st year onwards. Fabrication Works:
11. Under Contractor / Supplier scope .Design will be provided by Contractor / Supplier for approval from LCMC making the fabrication according to the location.
12. If the Crane and other services is required Contractor / Supplier must assure about this one.
13. After Sale Services: 1 years
14. Annual maintenance charges applicable after 2 year from installation.
15. Flat cables, SMP and module will be provided along with the screen for immediate changes.
16. Servicing of the screen will be provided within 4 working days after the complaint is registered and the photo is provided by the Contractor / Supplier to the issue faced on the screen.
17. Ensure that the available connected KVA load from SEB is available as per the rating of the Screen. If Connected Load is less than it is client responsibility to get the additional KV A load sanctioned from the SEB.
18. Electrical person will have to be provided during the installation of the screen.
19. Material required: 3 core cables as per rating, MCB as per rating, Switch Board with socket (Electrical Cable from the meter to the screen will have to be provided)
20. LAN Cable if required will have to provide by the Contractor / Supplier .
21. Stabilizer/UPS:
22. Contractor / Supplier shall use of Stabilizer/UPS for increase in life of LED Screen.
23. Stabilizer/UPS will stabilize Power fluctuations
24. Approvals shall be taken from Nodal Officer NCAP, Latur City Municipal Corporation, Latur

*Specification checked
Santosh
Env. consultant.*

A. Mayur
**Deputy Commissioner
And Nodal Officer NCAP
Latur City Municipal Corporation,**